


District Cooling for Honolulu's CBD

--Then and Now--




Agenda

- ◆ *The demand for cooling*
- ◆ *Response(s) To-date*
- ◆ *What is district cooling?*
- ◆ *Development to date*
- ◆ *Benefits*
- ◆ *Next Steps*



The Cooling Opportunity

- ◆ ***Many chillers are at the end of their useful life***
- ◆ ***Clean Air Act banned the manufacture of CFCs***
- ◆ ***Additional regulations are on the way***
- ◆ ***Hard to find capital for non-core business investments***



Possible Solutions

- ↓ **Stockpile CFCs, do nothing**
- ↓ **Rebuild chillers for use with other refrigerants**
- ↓ **Replace chillers and refrigerants**
- ↑ **Outsource cooling requirements!**



Stockpile CFCs


◆ Stockpile CFCs-

- Hedges against cost increases***
- Entails additional risk***

◆ Wait for a better answer


◆ Replace/rebuild costs increase

◆ Regulations/fines increase



The Demand for Cooling

- ◆ ***Air conditioning***
- ◆ ***Process cooling***
 - ***Computers***
 - ***Communications***
- ◆ ***Refrigeration***
 - ***Walk-in coolers***
 - ***Cold storage***



Rebuild Chillers

- ◆ ***Rebuild chillers/replace refrigerants***
- ◆ ***A “retrofit”-technically difficult***
- ◆ ***Probable capacity reduction***
- ◆ ***Limited life, unknown problems ahead***
- ◆ ***Risky refrigerant choices***
- ◆ ***Capital used for non-core cost center***
- ◆ ***Can be expensive!***

Replace Chillers


- ◆ ***Difficult to remove and install***
- ◆ ***Complex, difficult to manage project***
- ◆ ***Replace chillers and refrigerants***
- ◆ ***Risky refrigerant choices***
- ◆ ***Capital used for non-core cost center***
- ◆ ***Can be very expensive!***

Outsource Cooling

- ◆ ***Eliminates building cooling plant-***
 - ***Capital requirements***
 - ***Operating and maintenance concerns***
 - ***Environmental risk***
- ◆ ***Allows greater focus on core business!***



What is District Cooling?



What is District Cooling?

- ◆ ***Centrally-supplied chilled water***
 - ***Available 24 hours/day, 365 days/year***
 - ***Totally meets building owner needs***
- ◆ ***Environmentally sound solution***
 - ***Eliminates building cooling plant CFCs, emissions, noise, plume***
 - ***Reduces ozone depletion and global warming***
 - ***Improves cooling efficiency***
- ◆ ***Easy Building Syndrome!!***



What is District Cooling?

◆ Reliable service

- ***Proven, dependable technology***
- ***Interruptions virtually non-existent***
- ***40 North American commercial systems***
- ***2000 North American institutional systems***
- ***Also in Europe and Asia***

◆ Growth industry

- ***Growth rate of at least 15% annually***
- ***Most growth since 1990***

◆ Catalyst for economic development

- ***More competitive CBD***
- ***Bring jobs to the CBD***

District Cooling Development Options

◆ *Utilities*

- ***Electric***
- ***Gas***


◆ *Municipalities*

- ***Municipal utilities***
- ***Not-for-profit development companies***

◆ *Independents*

- ***Entrepreneurial energy companies***
- ***Customer cooperatives***

◆ *Hybrids of above*




Responses To-date in 40+ North American Cities (so far)

- ◆ ***Educate & Energize Community leadership—public & private sectors!***
- ◆ ***Decide to meet customer needs by establishing a District Cooling service***
- ◆ ***Initiate process to begin operations in about 14-18 months***
- ◆ ***Initially focus on the downtown areas***



District Cooling Growth



Community Leadership

- ◆ ***Got to have it!!***
- ◆ ***Has come from public and private sectors***
- ◆ ***Based on what's good for the community***
- ◆ ***Sees the economic development benefits***
- ◆ ***Often easier to educate than to energize***




Customer Needs

- ◆ ***A lot more than just air conditioning!!***
- ◆ ***Eliminate and contain capital costs***
- ◆ ***Reduce surprises & increase reliability***
- ◆ ***Make building easier to own & operate***
- ◆ ***Get cooling where needed, when needed***
 - ***24/7 operation***
 - ***Special events***
 - ***After hours cooling***
 - ***Data centers***

Risk Management
Risk Management

Operating in 14-18 Months??

- ◆ ***After anchor customers signed up!!***
- ◆ ***If you build it, they will come works in the movies—No “Field of Dreams”***
- ◆ ***Process includes***
 - ***Business appreciation study***
 - ***Technical & financial feasibility***
 - ***Service agreement terms***
 - ***Customer discussions, customer discussions, & concurrence***



Initial Focus


- ◆ ***Downtown areas, Honolulu CBD***
- ◆ ***Actually, Campus Areas***
 - ***Educational***
 - ***Health Care***
 - ***Governmental***
 - ***Industrial***
 - ***Downtown***

Building Density


Project Description

- ◆ ***Four parts-a target market area, sources of chilled water, distribution network, and connections to customers' buildings***
- ◆ ***Target Markets**-Central Business Districts, educational and health care campuses*
- ◆ ***Sources**-chilled water plants, selected customer equipment, thermal storage, deep lakes, oceans*
- ◆ ***Distribution Network**-buried pipes: steel, ductile iron, HDPE*
- ◆ ***Connections**-heat exchangers, metering and controls installed in customers' buildings*

Potential Area for District Cooling



HONOLULU PHASING



CLIENT: **Entergy**
Entergy Thermal, LLC

PROJECT: **DOWNTOWN HONOLULU DISTRICT COOLING DEVELOPMENT**

- PHASE A
- PHASE B
- PHASE C
- PHASE D

Bldg ID	Bldg Name
2	State Capitol
4	State Buildings (4)
6	1100 Alaska
8	Verizon-Hawaii
10	Century Square
12	Finance Factors
14	1132 Bishop
16	Executive Center
18	Bishop/Gasco
20	Liberty House
22	Bishop Square
24	Central Pacific Plaza
26	Aili Tower
28	Bank of Hawaii
30	Pioneer Plaza
32	Harbor Court
34	Campbell Building
36	Davies Pacific Center
38	Grosvenor Center
40	AMFAC
44	Kinai Hale
46	Hawaii State Library
48	Honolulu Hale
50	Kalanimoku Bldg
52	Honolulu Medical Group
54	Municipal Bldg

REVISIONS

0 PRELIMINARY ISSUE 06/30/01
NO. REMARKS DATE

KATNER/FVB
DISTRICT ENERGY INC.
150 SOUTH FIFTH STREET, SUITE 340
MINNEAPOLIS, MINNESOTA 55402
TEL: (612) 338-4489 FAX: (612) 338-3427

This document is the property of Katner/FVB District Energy Inc. and the information herein is not to be used or copied, except for the specific project it was issued, without the written authorization of Katner/FVB District Energy Inc.

POTENTIAL CUSTOMER PHASING MAP

DESIGNED BY: TL
DRAWN BY: JLC
APPROVED BY: JLC
DATE: 9/14/01

SCALE: 1"=250'
JOB NO.: 501227
DRAWING NO.:
MAP-3

Chilled Water Sources

- ◆ ***Initial phase with expansion of selected existing chilled water plant(s)***
- ◆ ***Expansion to new plant with large, efficient, industrial-grade chillers with thermal storage (ice), or***
- ◆ ***Expansion to chilled water storage tank, or***
- ◆ ***Expansion to ocean water based cooling, or***
- ◆ ***Creative combinations***


Chilled Water Plants

- ◆ ***25,000 ton CHW plant***
 - ***7,000 tons from ice***
 - ***18,000 tons from mechanical cooling***
- ◆ ***State and Adams St., Chicago, IL***
- ◆ ***Subsidiary of Unicom Corporation***



Chilled Water Plants

- ◆ **20,000 ton CHW plant**
 - 5,000 tons from ice
 - 15,000 tons from mechanical cooling
- ◆ **15th and Glenarm, Denver, CO**
- ◆ **Public Service Co. of Colorado**



Chilled Water Plants

◆ ***32,000 ton plant***

- ***52,000 t-hrs of storage***
- ***20,000 tons of chillers***

◆ ***600 car parking***


◆ ***8MWe stand-by***

◆ ***Medical Center***

◆ ***Entergy-New Orleans***



PRELIMINARY PLANT GENERAL ARRANGEMENT



NOT FOR CONSTRUCTION

REVISIONS		
NO.	REVISIONS	DATE
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		

DATE: _____
 REMARKS: _____
 NO.: _____

This document is the property of FVB Energy Inc. and the information herein is not to be used or copied except for the specific project it was issued without the written authorization of FVB Energy Inc.

FVB
ENERGY INC.
 150 SOUTH FIFTH STREET, SUITE 340
 MINNEAPOLIS, MINNESOTA 55402
 TEL: (612) 338-4489
 FAX: (612) 338-3427

Commercial Deep Water Cooling

- ◆ ***Cornell University – fresh water lake***
- ◆ ***Enwave Toronto – fresh water lake***
- ◆ ***Stockholm – Baltic Sea plus heat pumps***
- ◆ ***Sollentuna -- sea water plus aquifer storage***
- ◆ ***Uppsala Väsby – deep water plus heat pump***
- ◆ ***Nacka Strand – sea water***
- ◆ ***Norrenergi – sea water***

Telgi Energi – Södertälje, Sweden

- ◆ ***Cold water from Lake Mälaren provides cooling to a large pharmaceutical plant and other commercial customers***
- ◆ ***Production capacity 17,000 tons***
- ◆ ***Supply temperature less than 48F all year long***
- ◆ ***Source depth 148 ft***
- ◆ ***Supply flow rate 26,400 gpm***
- ◆ ***District cooling distribution 3.7 miles of 39 inch diameter polyethylene pipe***

Pipe installation in Lake Mälaren



Sea Water Cooling in Stockholm




Distribution Network



- ◆ ***Closed system-water supplied is recycled and closely monitored for quality and quantity***
- ◆ ***Two buried pipes-supply and return***
- ◆ ***Piping material depends on subsurface conditions***
- ◆ ***Chilled water supply is at 34-40°F, return at 50-54°F***
- ◆ ***Includes conduits for communications***

Typical Trench Detail for Chilled Water Pipes in City Streets



Distribution System

- ◆ ***Typical distribution installation***
- ◆ ***Public Service Company of Colorado, Denver***
- ◆ ***24" Epoxy-coated welded steel pipe***




Customer Connections


- ◆ **Eliminated-building chillers, cooling towers and refrigerants**
- ◆ **Installed-heat exchangers, piping, controls and metering**
- ◆ **Operations-clean, quiet, environmentally safe and easy**
- ◆ **Reliability-proven equipment, fewer moving parts**

Connections

- ◆ *Typical connection in Chicago*
- ◆ *30 story building, 850 ton peak cooling load.*
- ◆ *Two heat exchangers, piping, valves, controls*
- ◆ *Clean, quiet, zero emissions*




Connections



- ◆ ***Easily increase capacity by adding plates***
- ◆ ***Building and District Cooling water are separated***
- ◆ ***Control systems set for desired temperatures***

TYPICAL INDIRECT INTERCONNECTION SCHEMATIC



Building Owner Benefits

◆ **No capital risk** to
replace or rebuild

◆ **No operating risk**
to operate and
maintain a plant

- Maintenance and repairs
- Chemicals
- Water

• Insurance and taxes

• Labor

• Security

◆ **No refrigerant risk**

• Selection

• Disclosure

• Storage

• Handling

Building Owner Benefits

◆ Improves cooling performance

- Quick response
 - Cool down following a hot weekend
 - Abrupt changes in temperature
- Available 24 hrs per day, 365 days per year
- Improves comfort in previously hard to cool spaces
- Opportunity to decrease building energy use
- After hours cooling easier and more economical

Building Owner Benefits

◆ Improves reliability

- ***Multiple industrial-grade chillers***
- ***High reliability design***
- ***Machines and storage***
- ***Distribution network***

◆ Eliminates environmental concerns


- ***Refrigerants, water treatment chemicals***
- ***Noise, vibration, health and safety issues***
- ***Water use***
- ***Wastewater discharges***

Building Owner Benefits

- ◆ Releases space for more productive uses
- ◆ Increases security by reducing service vendors and vehicles
- ◆ Easier building to own, operate and maintain
- ◆ More predictable financially, operationally
- ◆ Allows focus on core business!



Ultimate Development



City of Honolulu Benefits

◆ Supports economic development

- *Adds new infrastructure and business to the CBD*
- *New projects no longer need cooling plants*
- *Renovations can focus \$\$ on competitiveness*
- *Local construction jobs*
- *Long-term district cooling employment*



City of Honolulu Benefits

◆ Adds new opportunities-

- ***Thermal storage to reduce electric demand and \$\$***
- ***Ocean water as renewable energy source***
- ***Conservation of freshwater***

◆ Eliminates-

- ***Deteriorated cooling towers***
- ***Aged chillers***
- ***Stress on local electric utility distribution system***

Summary


◆ ***District Cooling is...***

- ***A proven way to cool educational, health care, industrial and urban campuses***
- ***A flexible system that works well with thermal storage and sea water for AC***
- ***A financial, operational and environmental risk management strategy***

Summary


◆ *District Cooling is...*

- *Good for the end-users*
- *Good for Honolulu*
- *Good for Hawaii*



District Cooling for Honolulu

—*Tomorrow ??*—



Why Ice Storage?




- ◆ ***Reduces investment costs***
 - ***Smaller distribution pipes***
 - ***Smaller connection equipment***
- ◆ ***Shifts some cooling to off-peak***
- ◆ ***Provides low temperature CHW***
- ◆ ***An extra measure of redundancy***
- ◆ ***Makes sense to the public!***

City of Honolulu Benefits

◆ Improves environmental compliance

- ***Large, efficient, industrial-grade chillers***
- ***Refrigerants-minimum ODP and GWP***
- ***Minimum noise and plume production***
- ***Experienced staff dedicated to CHW production***



Summary

◆ **Good for customers!**

- **Satisfies a need**
- **Eliminates environmental concerns**
- **Improves cooling performance**
- **Increases reliability**

◆ **Good for the city!**


- **Supports economic development**
- **Beautifies the city**
- **Improves the environment**

A Winning Solution!

Pump station installed on rock in shallow water in Lake Mälaren



Distribution System-typical



Sollentuna Energi – Sollentuna, Sweden

- ◆ ***Production capacity 1,100 tons***
- ◆ ***Aquifer storage capacity 730,000 ton-hrs***
 - ***Supply temperature 45F***
 - ***Source depth 50 feet***
- ◆ ***Pipe materials***
 - ***Polyethylene for pipe installed in the bay***
 - ***Carbon steel for underground pipe***
 - ***Stainless steel for customer connections***

Integration of Deep Water Cooling and Seasonal Aquifer Storage -- Sollentuna

